BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/08/2016-17 Dated: 4-03-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 43

Name of Work:-: Maintenance of Existing borewells at village limit areas in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G MUNIRAJU	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	163.80	200.00	Rupees two hundred only
2	Providing and fixing to wall, ceiling and floor, high density polyethylene pipes 6.00 kgs/sq.cm working pressure 75mm outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications.(P.N.93) 75 mm dia (It.no.13.703)	Rmtr	200.00	320.00	Rupees three hundred twenty only
3	63mm dia (It.no.13.70.2)		255.00	278.00	Rupees two hundred seventy eight only
4	Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P. No.6 I.No.2.11)	cum	163.80	80.00	Rupees eighty only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G MUNIRAJU	
				Rate	Rate in Words
5	Supply and delivery of submersible pump sets suitable for borewell of 165 mm dia with specified dyty conditions as detailed below and satisfying performance characteristics for pump and moter specified in BIS with ISI mark with a minimum efficiency of 42% pump shall confirm to IS 8034/2002 and motor conforming to IS 9283/1995 with ISI certification with latest amendments for the following.15.0HP/11KW ATALANTA/SUGUNA/CRI/KIRLOSKAR /OTHER EQUIVALENT PUMPS (page no.XXXXII / Sl.No.33 Code No.2)2016-17	set	5	70600.00	Rupees seventy thousand six hundred only
6	Providing, GI pipe50mm dia B class (Page.No XVII Sl.no.509, code no.0154)	Rmtr	150.00	300.00	Rupees three hundred only
7	Providing & fixing R-socket GI pipe fitting (Page.No XXXIX) GI FITTINGS TABLE)	No	45.00	92.00	Rupees ninety two only
8	Supplying and drawing 3 crore flat PVC submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 to IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts.)P.No.49/ It.No.29c(1) 2.5sqm of 36 strands 0.3mm dia group-A KPWD Electrical SR 2014-15	Mtr	300.00	178.00	Rupees one hundred seventy eight only
9	Gun metal non-return valve 50mm nominal bore horizontal pipe (Page.No XXII Sl.no.659, code no.0126)	No's	11	1140.00	Rupees one thousand one hundred forty only
10	Gate valve 50mm nominal bore gun metal (Page.No XXII Sl.no.673, code no.0164)	No's	12	1650.00	Rupees one thousand six hundred fifty only
11	Providing & fixing of Union 50mm for GI pipe fitting (Page.No XXXIX) GI FITTINGS TABLE)	No's	12	223.70	Rupees two hundred twenty three and paise seventy only
12	Providing and fixing of 50mm GI Nipple to motor (Page.No XXXIX) GI FITTINGS TABLE)	No's	12	104.11	Rupees one hundred four and paise eleven only
13	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	Per length	200.00	90.05	Rupees ninety and paise five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.